

Garrett Rhodes Electrical Services, Inc.
P.O. Box 1424
Port Richey, FL 34673-1424
Lic. # EC-13005613

Phone # 727-856-6962

Estimate

Date	Estimate #
3/19/2020	835

Name / Address
CITY OF NEW PORT RICHEY 5919 MAIN ST. NEW PORT RICHEY, FL 34652

JOB LOCATION:
CITY HALL GENERATOR INSTALL

Project		GENERATOR	
Description	Qty	Each	Total
INSTALL (CUSTOMER SUPPLIED) 50 KW DIESEL GENERATOR 120/208 VOLT 3-PHASE (132 GALLON TANK). INSTALL (CUSTOMER SUPPLIED) AUTOMATIC TRANSFER SWITCH. INSTALL NECESSARY CONDUIT AND CABLING FROM GENERATOR TO TRANSFER SWITCH. RELOCATE CIRCUIT FOR PANEL 2SB TO AUTOMATIC TRANSFER SWITCH. CUSTOMER IS RESPONSIBLE FOR REMOVAL OF LANDSCAPING, GRADE WORK, CONCRETE SLAB, SETTING GENERATOR, AND FUELING GENERATOR. RELOCATE U.P.S. CIRCUITS FROM PANEL 2SA TO 2SB.	1	15,500.00	15,500.00
STARTUP AND TESTING	1	750.00	750.00
*ALL WORK WILL BE COMPLETED DURING BUSINESS HOURS.			
Thank you for your business.		Total \$16,250.00	

Signature _____



C.E.S. (Hudson FL)
9121 Eden Ave., North Hudson, FL,
34667.

Phone: 727-863-0707
Fax: 727-868-6519
Email: Hudson0194@cityelectricsupply.com

CITY ELECTRIC SUPPLY

GARRETT RHODES ELECTRICAL

GENERAL ACCOUNT
P.O. BOX 1424
PORT RICHEY FL
34673
Phone: 727-856-6962
Fax: 727-842-7227

Delivery Details:
MUST HAVE PROPER PO FROM
GARRETT

QUOTATION

HUD/009962

Valid From: 26 Mar 2020
Valid Until: 25 Apr 2020

Page 1/1

Entered by: William Wood Jr
Sales Rep: William Wood Jr

Account No.: 01940288001
Order Number: DIESEL

Qty	Item	Description	\$ Price Per	\$ Goods
1	GENERAC RD05034	50 KW, 1800Rpm, 30 Only, Aluminum Encl	15922.00 1	15922.00
1	GENERAC RTSW200J3	200A SERVICE RATED 120/240 3/0 N3R	1899.00 1	1899.00

actual part number rd05034gdal
largest tank 138 gallon

Please do not hesitate to contact us if we can be of any further assistance.

Sincerely Yours,

William Wood Jr

(QUOTE ONLY. NOT A RECEIPT) Goods Total: \$17821.00

Prices may be subject to change from manufacturer at the time of dispatch. When ordering please use above quotation number.
Seller assumes no responsibility for quoted materials meeting job specifications unless specifically stated in writing.
Substitution of similar quality material is permitted. All special order material is non-returnable or subject to the manufacturer's return goods policy.



Farrell Power Company

City New Port Richey
5919 Main St
New Port Richey, FL 34652

(727) 597-0276
riverar@cityofnewportricher.org

ESTIMATE
SCHEDULED DATE

#91
Mon Apr 6, 2020
9:00am

TOTAL

\$35,936.00

CONTACT US

6835 Commerce Ave
Port Richey, FL 34668

(727) 847-6937
matt@goteamfarrell.com

ESTIMATE

Services	Amount
Generator Estimate	\$35,936.00
Install Model RD050 50K diesel (Larger tank) generator with 200A transfer switch. Tie in to 150A feed for IT for continuous power. All materials and labor per scope of job. Generator pad. Permitting. Coordination with power company.	
Total	\$35,936.00

Thank you for your business!



Make Checks Payable to:
MCWILLIAMS AND SON, INC.
6211 SPRINGER DR. • PORT RICHEY, FL 34668
(727) 862-7002
Lic. CAC1814314
Lic. EEC13007378

24625

☐ REFRIGERATION

☒ HVAC ☒ ELECTRICAL

☐ CASH ☐ CHECK ☐ CHARGE

• SERVICE ALL MAKES • RESIDENTIAL & COMMERCIAL

Trans. #

NAME

Mike DeLase / City Hall NPK

Date 4-1-2010

ADDRESS

5919 Main St.

Phone 727-597-0276

Customer's P.O.

Job City Hall Generator

Est. McWilliams & Son, Inc. 4/1/2010

☐ Service

☐ ATC

☐ GARAGE

☐ POOF

☐ VERT

☐ HORIZ

CITY, STATE, ZIP

New Port Richey FL 34652

COND.

MOD. #

SER. #

MAKE

MOD. #

SER. #

MAKE

A/H

MOD. #

SER. #

MAKE

MOD. #

SER. #

MAKE

1-50KW 120/208 3phase Generac Generator 70DB Quiet Diesel Generator with 138.5 Gallon tank Dimensions L-95" W-35" H-57". This generator is for Panel 25A for data equipment. The generator will be located on west side of property land clearing and slab will be done by other. Items included in estimate are: Generator, 3/4 200 amp transfer switch, Conduit from Generator to transfer switch, Conduit from transfer switch to MDP. Copper wire, Moving up to 8 circuits from panel next to panel 25A into panel 25A, Generator start up and Generator Test. 1 year labor and 5 year Generac warranty.

QUAN.

MATERIALS

PRICE

QUAN.

MATERIALS

PRICE

Any Questions Call
Thank you,
Todd Smith
727-243-7276

Payment due in full upon completion of work, unless extended terms are mutually agreed upon before work commences. Any and all new equipment not paid for remains the property of McWilliams & Son, Inc. until fully paid for. Any balance of payment not received within 30 days from date of completion will be assessed an additional 1% interest per month on the balance until fully paid. McWilliams & Son, Inc. shall be entitled to recover from purchaser all costs, including all attorney's fees, for collection of any sums remaining unpaid. McWilliams & Son, Inc. shall not be obligated to perform any warranty repairs until invoice is paid in full.

I hereby acknowledge that I am authorized to sign for the above work and do hereby agree to the terms stated above in this contract.

SIGNATURE: (I hereby acknowledge the satisfactory completion of the above described work.)

MECHANIC

HELPER

TOTAL

31,995.00

WORK:

RECOMMENDATIONS: